



■ Features :

- Universal AC input / Full range
- Built-in active PFC function, PF>0.95
- High efficiency up to 88%
- Withstand 300VAC surge input for 5 seconds
- Protections: Short circuit / Overload / Over voltage / Over temperature
- · Cooling by free air convection
- · Built-in constant current limiting circuit
- 1U low profile 38mm
- · Built-in remote ON-OFF control
- Stand by 5V@0.3A
- · Built-in remote sense function
- No load power consumption<0.5W (Note.6)
- 5 years warranty




SPECIFICATION MODEL HRPG-150-3.3 HRPG-150-5 HRPG-150-7.5 | HRPG-150-12 | HRPG-150-15 | HRPG-150-24 | HRPG-150-36 | HRPG-150-48 DC VOLTAGE 3.3V 5V 7.5V 12V 15V 24V 36V 48V RATED CURRENT 30A 26A 20A 13A 10A 6.5A 4.3A 3.3A **CURRENT RANGE** 0 ~ 30A 0 ~ 26A 0 ~ 20A 0 ~ 13A 0 ~ 10A 0 ~ 6.5A 0 ~ 4.3A 0 ~ 3.3A RATED POWER 99W 130W 150W 156W 150W 156W 154.8W 158.4W RIPPLE & NOISE (max.) Note.2 80mVp-p 80mVp-p 100mVp-p 120mVp-p 150mVp-p 150mVp-p 200mVp-p 240mVp-p OUTPUT **VOLTAGE ADJ. RANGE** 2.8 ~ 3.8V 4.3 ~ 5.8V 6.8 ~ 9V 10.2 ~ 13.8V 13.5 ~ 18V 21.6 ~ 28.8V 28.8 ~ 39.6V 40.8 ~ 55.2V **VOLTAGE TOLERANCE Note.3** $\pm 2.5\%$ ±2.5% ±2.5% ±1.5% ±1.5% ±1.5% ±1.5% $\pm 1.5\%$ LINE REGULATION $\pm 0.5%$ +0.5% +0.5% +0.3% +0.3%+0.2% $\pm 0.2\%$ $\pm 0.2\%$ LOAD REGULATION $\pm 1.0\%$ ±1.0% $\pm 1.0\%$ $\pm 0.5\%$ $\pm 0.5\%$ $\pm 0.5\%$ $\pm 0.5\%$ $\pm 0.5\%$ SETUP, RISE TIME 3000ms, 50ms/230VAC 3000ms, 50ms/115VAC at full load HOLD UP TIME (Typ.) 16ms/230VAC 16ms/115VAC at full load **VOLTAGE RANGE** Note.5 85 ~ 264VAC 120 ~ 370VDC 47 ~ 63Hz FREQUENCY RANGE PF>0.95/230VAC PF>0.99/115VAC at full load POWER FACTOR (Typ.) INPLIT 84% 88% 88% EFFICIENCY (Typ.) 78.5% 86% 87% 87% AC CURRENT (Typ.) 2.3A/115VAC 1.3A/230VAC INRUSH CURRENT (Typ.) 70A/230VAC 35A/115VAC LEAKAGE CURRENT <1mA / 240VAC 105 ~ 135% rated output power **OVERLOAD** Protection type: Constant current limiting, recovers automatically after fault condition is removed 6 ~ 7V 9.4 ~ 10.9V 41.4 ~ 48.6V 57.6 ~ 67.2V **PROTECTION OVER VOLTAGE** Protection type: Shut down o/p voltage, re-power on to recover **OVER TEMPERATURE** Shut down o/p voltage, recovers automatically after temperature goes down **5V STANDBY** 5VSB:5V@0.3A; tolerance ±5%, ripple:50mVp-p(max.) **FUNCTION** RC+ / RC-: $4 \sim 10V$ or open = power on ; $0 \sim 0.8V$ or short = power off REMOTE CONTROL WORKING TEMP. -40 ~ +70°C (Refer to "Derating Curve") 20 ~ 90% RH non-condensing **WORKING HUMIDITY** ENVIRONMENT -40 ~ +85°C, 10 ~ 95% RH STORAGE TEMP., HUMIDITY TEMP. COEFFICIENT ±0.04%/°C (0 ~ 50°C) VIBRATION 10 ~ 500Hz, 5G 10min./1cycle, 60min. each along X, Y, Z axes UL60950-1, TUV EN60950-1 approved SAFETY STANDARDS WITHSTAND VOLTAGE I/P-O/P:3KVAC I/P-FG:2KVAC O/P-FG:0.5KVAC SAFETY & ISOLATION RESISTANCE I/P-O/P, I/P-FG, O/P-FG:100M Ohms / 500VDC / 25°C / 70% RH **EMC** (Note 4) **EMC EMISSION** Compliance to EN55022 (CISPR22) Class B, EN61000-3-2,-3 **EMC IMMUNITY** Compliance to EN61000-4-2,3,4,5,6,8,11, EN55024, EN61000-6-2, heavy industry level, criteria A MTBF 213.4K hrs min. MIL-HDBK-217F (25°C) **OTHERS DIMENSION** 159*97*38mm (L*W*H) **PACKING** 0.63Kg; 24pcs/16Kg/0.76CUFT All parameters NOT specially mentioned are measured at 230VAC input, rated load and 25°C of ambient temperature. NOTE 2. Ripple & noise are measured at 20MHz of bandwidth by using a 12" twisted pair-wire terminated with a 0.1uf & 47uf parallel capacitor. 3. Tolerance: includes set up tolerance, line regulation and load regulation.

- 4. The power supply is considered a component which will be installed into a final equipment. The final equipment must be re-confirmed that it still meets EMC directives. For guidance on how to perform these EMC tests, please refer to "EMI testing of component power supplies."

 (as available on http://www.meanwell.com)
- 5. Derating may be needed under low input voltages. Please check the derating curve for more details.
- 6. No load power consumption<0.5W when RC- & RC+ (CN100 pin5,6) 0 \sim 0.8V or short.







■ Function Description of CN100


Pin No.	Function	Description
1		Negative sensing. The -S signal should be connected to the negative terminal of the load. The -S and +S leads should be twisted in pair to minimize noise pick-up effect. The maximum line drop compensation is 0.5V.
2		Positive sensing. The +S signal should be connected to the positive terminal of the load. The +S and -S leads should be twisted in pair to minimize noise pick-up effect. The maximum line drop compensation is 0.5V.
3	AUXG	Auxiliary voltage output ground. The signal return is isolated from the output terminals (+V & -V).
4	AUX	Auxiliary voltage output, 4.75~5.25V, referenced to pin 3(AUXG). The maximum load current is 0.3A. This output is not controlled by the "remote ON/OFF control".
5	RC-	Remote control ground.
6	RC+	Turns the output on and off by electrical or dry contact between pin 5 (RC-). Short: Power OFF, Open: Power ON.

■ Function Manual

1.Remote Control

The PSU can be turned ON/OFF by using the "Remote ON/OFF" function $% \left(\frac{1}{2}\right) =\frac{1}{2}\left(\frac{1}{2}\right) =\frac{1}{2}\left$

Between RC-(pin5) and RC+(pin6)	Output Status
SW ON (Short)	OFF
SW OFF (Open)	ON




CN100

6 RC+ AUX +S 2
5 RC- AUXG -S 1

Fig 1.1

2.Remote Sense

The remote sensing compensates voltage drop on the load wiring up to 0.5 V.



CN100

6 RC+ AUX +S 2

5 RC- AUXG -S 1

Fig 2.1